

External Water-Bar Installation – National Starch, Karasin



Whether damaged during installation, incorrectly detailed or omitted all together, the failure of the waterproofing at the main construction joint between two primary waste water treatment tanks caused major problems for National Starch maintenance staff in Karasin.

The solution proposed by Hammersmith was the post installation of the Dila Joint Tape System from Messrs. Vandex International

Our unrivaled experience in the fields of polyurethane injection, concrete repair, waterproof membrane installation, expansion joint detailing and access to specifically designed materials allow us to offer a complete joint sealing service.

Repair Sequence Key

- 1 Failed construction joint
- 2 First pass PU injection
- 3 Forming chase
- 4 Second Pass PU injection
- 5 Installation
- 6 Surface repair



HAMMERSMITH LIMITED

38/1 Soi Naphasap Yak 1 Sukhumvit Soi 36,

Klongtoey, Bangkok 10110 THAILAND

Phone: (662) 661 5962/3

Fax: (662) 661 5986

Email: email@hammersmithgroup.com

Web: www.hammersmithgroup.com

